

City of New London

Department of Finance-Purchasing Agent
13 Masonic Street • New London, CT 06320 • Phone (860) 447-5215 • Fax (860) 447-5297

Invitation for Bids

ADDENDUM No. 2

Bid No.: 2015-09

Addendum No.: 2

Date Issued: October 17, 2014

NLPD Exterior Concrete Staircase Removal and Replacement

Opening Date and Time: Friday, October 24, 2014 at 2:00 P.M.

Bidders Notes: This addendum is issued to provide all bidders with notice of revisions/additions to the General Conditions and Specifications.

All other terms and conditions remain the same.

This Addendum cover page must be signed and returned with your bid.


Authorized Signature of Bidder

Company Name

Return Bid To:

Alicia Smith, Purchasing Agent
City of New London
13 Masonic Street
New London, CT 06320

Bids cannot be accepted after the Bid Opening Date and Time indicated above.



City of New London

Department of Finance-Purchasing Agent
13 Masonic Street • New London, CT 06320 • Phone (860) 447-5215 • Fax (860) 447-5297

Revisions/Additions to General Conditions and Specifications

- 1) Revised Section 5.5 During the proposed construction, the Contractor shall provide maintenance and protection of the work areas, taking all necessary precautions to safely and carefully protect motorists, pedestrians, and the general public. *To provide a safe and alternate access to the building, the Contractor shall clean one half of the middle landing of the alternate exterior concrete staircase prior to the placement of a concrete skim coat.* The Contractor will be required to present a proposed construction schedule prior to commencement; as well as, provide written notification to the office listed above in Section 4.6 at least five (5) full working days prior to the proposed construction.
- 2) Revised Section 2.3 Bid Opening: *Friday, October 24, 2014*, 2:00 p.m., Purchasing Department, 13 Masonic Street
- 3) Add Section 5.6 Proposed finish treatments of the existing metal railings are not a part of this scope of work. Contractor shall remove and reinstall existing metal center railing as part of the scope of work. Existing metal center railing shall be removed by the Contractor and stored by the City of New London until reinstallation by the Contractor.
- 4) Add Section 5.7 The Contractor shall provide a concrete sidewalk patch, approximately 8 sf, in the area where the metal railing terminates at the base of the stairs.