



# City of New London

Department of Finance-Purchasing Agent  
13 Masonic Street • New London, CT 06320 • Phone (860) 447-5215 • Fax (860) 447-5297

## Invitation for Bids

### ADDENDUM 2

**Proposal No.:** 2021-03

**Addendum No.:** 2

**Date Issued:** October 15, 2020

**Intersection Improvements Tilley St. at Green St. and Bank St.  
State Project 094-260**

**Opening Date and Time:** October 20, 2020 at 2:00PM

**Bidders Notes:** This addendum is issued to provide all potential bidders with answers to questions regarding the bid form issued in addendum 1.

All other terms and conditions remain the same.

**This Addendum cover page must be signed and returned with your bid.**

\_\_\_\_\_  
Authorized Signature of Bidder

\_\_\_\_\_  
Company Name

**Return Bid To:**

Julie Chapman  
City of New London  
13 Masonic Street  
New London, CT 06320

**Bids cannot be accepted after the Bid Opening Date and Time indicated above.**

**2021-03 Tilley/Green/Bank St. Intersection Improvements**  
**State Project 094-260**

**Question 1:** Will there be an estimated cost provided for Item 0970006 traffic person (Municipal Police Officer)?

**Answer 1:** Please input \$22,000 for the estimated cost of the Traffic person (Municipal Police Officer).

**Question 2:** Are we to assume the items with +/-% are stated as these items cannot be any more than the % of the total base bid? (For example, Clearing and Grubbing can be no more than 2% of total bid)

**Answer 2:** No. Those percentages are just for the design engineer's reference only. They should not have been included on the bid list

**2021-03 Tilley/Green/Bank St. Intersection Improvements**  
**State Project 094-260**

| ITEM NO. | ITEM/DESCRIPTION                          | UNIT      | QTY | UNIT COST | TOTAL COST |
|----------|---|-----------|-----|-----------|------------|
| 0201001A | Clearing and Grubbing                     | L.S.      | 1   |           |            |
| 0202512  | Cut Concrete Sidewalk                     | LF        | 75  |           |            |
| 0202452A | Test Pits                                 | Ea.       | 8   |           |            |
| 0219011A | Sedimentation Control at Catch Basin      | Ea.       | 10  |           |            |
| 0202529  | Cut Bituminous Concrete Pavement          | LF        | 100 |           |            |
| 0406003A | Pavement Repair                           | SY        | 200 |           |            |
| 0507781  | Reset Manhole                             | Ea.       | 1   |           |            |
| 0811001  | Concrete Curbing                          | LF        | 200 |           |            |
| 0901003A | 4" Steel Bollard                          | Ea.       | 3   |           |            |
| 0921001  | Concrete Sidewalk                         | SF        | 125 |           |            |
| 0921005  | Concrete Sidewalk Ramp                    | SF        | 500 |           |            |
| 0921039  | Detectable Warning Strip                  | Ea.       | 5   |           |            |
| 0922050A | Decorative Crosswalk                      | SF        | 480 |           |            |
| 0969060A | Construction Field Office (Small)         | Month     | 4   |           |            |
| 0970006  | Traffic person (Municipal Police Officer) | Est. Cost | 1   | \$22,000  | \$22,000   |
| 0971001A | Maintenance & Protection of Traffic       | L.S.      | 1   |           |            |
| 0975004  | Mobilization and Project Closeout         | L.S.      | 1   |           |            |
| 0976002  | Barricade Warning Lights - High Intensity | Day       | 120 |           |            |

**2021-03 Tilley/Green/Bank St. Intersection Improvements**  
**State Project 094-260**

| ITEM NO. | ITEM/DESCRIPTION                                  | UNIT | QTY   | UNIT COST | TOTAL COST |
|----------|---|------|-------|-----------|------------|
| 0977001  | Traffic Cone                                      | Ea.  | 60    |           |            |
| 0978002  | Traffic Drum                                      | Ea.  | 30    |           |            |
| 0979003  | Construction Barricade Type III                   | Ea.  | 6     |           |            |
| 0980001  | Construction Staking                              | L.S. | 1     |           |            |
| 1001001A | Trenching and Backfilling                         | LF   | 1,100 |           |            |
| 1001004  | Rock in Trench Excavation 0'-4" Deep              | CY   | 15    |           |            |
| 1002015  | Rock in Foundation Excavation                     | VF   | 10    |           |            |
| 1102202A | Traffic Control Foundation - Mast Arm             | Ea.  | 4     |           |            |
| 1002203  | Traffic Control Foundation - Pedestal - Type I    | Ea.  | 11    |           |            |
| 1002208  | Traffic Control Foundation - Controller - Type IV | Ea.  | 1     |           |            |
| 1008015  | 2" Rigid Metal Conduit - Surface                  | LF   | 40    |           |            |
| 1008115  | 2" Rigid Metal Conduit in Trench                  | LF   | 350   |           |            |
| 1008117  | 3" Rigid Metal Conduit in Trench                  | LF   | 80    |           |            |
| 1008215  | 2" Rigid Metal Conduit Under Roadway              | LF   | 1100  |           |            |
| 1008217  | 3" Rigid Metal Conduit Under Roadway              | LF   | 375   |           |            |
| 1010001  | Concrete Handhole                                 | Ea.  | 9     |           |            |
| 1010021  | Concrete Handhole - Type 2                        | Ea.  | 13    |           |            |
| 1010052  | Cast Iron Handhole Cover                          | Ea.  | 9     |           |            |

**2021-03 Tilley/Green/Bank St. Intersection Improvements**  
**State Project 094-260**

| ITEM NO. | ITEM/DESCRIPTION                                   | UNIT | QTY | UNIT COST | TOTAL COST |
|----------|--|------|-----|-----------|------------|
| 1010054  | Cast Iron Handhole Cover - Type 2                  | Ea.  | 13  |           |            |
| 1102002A | 8' Aluminum Pedestal                               | Ea.  | 9   |           |            |
| 1102010A | 12' Aluminum Pedestal                              | Ea.  | 2   |           |            |
| 1104026A | 25' Steel Mast Arm Assembly                        | Ea.  | 1   |           |            |
| 1104028A | 30' Steel Mast Arm Assembly                        | Ea.  | 1   |           |            |
| 1104037A | 45' Steel Mast Arm Assembly                        | Ea.  | 2   |           |            |
| 1105103A | 1 Way, 3 Section Mast Arm Signal                   | Ea.  | 17  |           |            |
| 1105303A | 1 Way, 3 Section Pedestal Mounted Signal           | Ea.  | 2   |           |            |
| 1106002A | 2 Way Pedestrian Signal Pole Mounted               | Ea.  | 1   |           |            |
| 1106003A | 1 Way Pedestrian Signal Pedestal Mounted           | Ea.  | 6   |           |            |
| 1106004A | 2 Way Pedestrian Signal Pedestal Mounted           | Ea.  | 3   |           |            |
| 1107006  | Pre-Emption Push button                            | Ea.  | 1   |           |            |
| 1107011A | Accessible Pedestrian Signal and Detector (Type A) | Ea.  | 14  |           |            |
| 1108115A | Full Actuated Controller 8 Phase                   | Ea.  | 1   |           |            |
| 1108724A | Phase Selector                                     | Ea.  | 3   |           |            |
| 1111201A | Temporary Detection (Site No. 1)                   | L.S. | 1   |           |            |
| 1112284A | Vehicle Detection Monitor                          | Ea.  | 3   |           |            |
| 1112286A | 360 Degree Camera Assembly                         | Ea.  | 3   |           |            |

**2021-03 Tilley/Green/Bank St. Intersection Improvements**  
**State Project 094-260**

| ITEM NO. | ITEM/DESCRIPTION   | UNIT | QTY  | UNIT COST | TOTAL COST |
|----------|--|------|------|-----------|------------|
| 1112287A | 360 Degree Video Detection Processor                           | Ea.  | 3    |           |            |
| 1112410A | Detector Type A  | Ea.  | 5    |           |            |
| 1112470A | Pre-Emption System Chasis                                      | Ea.  | 2    |           |            |
| 1113004  | 2 Conductor, No. 8 AWG Type SE Style TW                        | LF   | 250  |           |            |
| 1113102  | 5 Conductor, No. 14 Cable                                      | LF   | 6500 |           |            |
| 1113103  | 7 Conductor, No. 14 Cable                                      | LF   | 3200 |           |            |
| 1113550A | Detector Cable Optical   | LF   | 1900 |           |            |
| 1113725A | 23 AWG 4 Twisted Pair Category 6 Cable                         | LF   | 750  |           |            |
| 1118012A | Removal and/or Relocation of Traffic Signal Equipment          | L.S. | 1    |           |            |
| 1118051A | Temporary Signalization (Site No. 1)                           | L.S. | 1    |           |            |
| 1206023A | Removal and Relocation of Existing Signs                       | L.S. | 1    |           |            |
| 1208931A | Sign Face - Sheet Aluminum - Type IX Retro-Reflective Sheeting | SF   | 36   |           |            |
| 1210101  | 4" White Epoxy Resin Pavement Markings                         | LF   | 550  |           |            |
| 1210102  | 4" Yellow Epoxy Resin Pavement Markings                        | LF   | 1000 |           |            |
| 1210107  | 8" Yellow Epoxy Resin Pavement Markings                        | LF   | 25   |           |            |
| 1210118  | Epoxy Resin Pavement Markings, Symbols and Legends             | SF   | 1500 |           |            |
| 1211001  | Removal of Pavement Markings                                   | SF   | 2300 |           |            |
| 1220027  | Construction Signs   | SF   | 525  |           |            |

**2021-03 Tilley/Green/Bank St. Intersection Improvements**  
**State Project 094-260**

| ITEM NO.                         | ITEM/DESCRIPTION | UNIT | QTY | UNIT COST | TOTAL COST |
|----------------------------------|------------------|------|-----|-----------|------------|
| <b>2020 CONTRACT ITEMS TOTAL</b> |                  |      |     |           |            |
|                                  |                  |      |     |           |            |
|                                  |                  |      |     |           |            |